

Road Project Specifications for Town of Casey

Crack Sealing Specifications: a $\frac{3}{4}$ " route by $\frac{3}{4}$ ", heat torch cleaning with a three inch over band to be bid by the job.

Shouldering Specifications: minimum of two foot wide gravel shoulder to asphalt mat swept, rolled then bladed through outer edge of shoulder.

Gravel specifications for all projects: 5% or better binder passed through 200 sieves